

# KARNDEAN DESIGNFLOORING ACOUSTICAL PERFORMANCE TEST REPORT

# **SCOPE OF WORK**

ASTM E90 AND ASTM E492 TESTING ON 4.5 MM LOOSELAY LLP109

# **SPECIMEN TYPE**

152 mm Concrete Slab with Suspended Ceiling

### **REPORT NUMBER**

P1663.01-113-11-R0

## **TEST DATE**

08/29/22

## **ISSUE DATE**

10/05/22

## RECORD RETENTION END

08/29/26

### **PAGES**

15

# **DOCUMENT CONTROL**

RTTDS-R-AMER-Test-2844 (03/23/22) © 2017 INTERTEK





Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

## TEST REPORT FOR KARNDEAN DESIGNFLOORING

Report No.: P1663.01-113-11-R0

Date: 10/05/22

## **REPORT ISSUED TO**

## KARNDEAN DESIGNFLOORING

1100 Pontiac Court, Bushy Run Corporate Park Export, Pennsylvania 15632

### **SECTION 1**

### **SCOPE**

Architectural Testing, Inc. (an Intertek company) dba Intertek Building & Construction (B&C) was contracted by Karndean Designflooring to perform testing in accordance with ASTM E90 AND ASTM E492 on 4.5 mm LooseLay LLP109. Results obtained are tested values and were secured by using the designated test methods. Testing was conducted in the VT test chambers at Intertek B&C located in York, Pennsylvania.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

### **SECTION 2**

# **SUMMARY OF TEST RESULTS**

DATA FILE NO.	21663.01		
SERIES/MODEL:	.5 mm LooseLay LLP109		
STC	62		
IIC	57		
HIIC	56		

COMPLETED BY:	Michael A. Unnone	<b>COMPLETED BY:</b>	Daniel B. Mohler
	Technician - Acoustical		Project Lead - Acoustical
TITLE:	Testing	TITLE:	Testing
SIGNATURE:		SIGNATURE:	
DATE:	10/05/22	DATE:	10/05/22

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of ACCREDITED the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.





Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

## TEST REPORT FOR KARNDEAN DESIGNFLOORING

Report No.: P1663.01-113-11-R0

Date: 10/05/22

### **SECTION 3**

### **TEST METHODS**

The specimen was evaluated in accordance with the following:

**ASTM E90-09 (2016)**, Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions

ASTM E413-16, Classification for Rating Sound Insulation

**ASTM E492-09(2016)e1**, Standard Test Method for Laboratory Measurement of Impact Sound Transmission Through Floor-Ceiling Assemblies Using the Tapping Machine

**ASTM E989-21**, Classification for Determination of Impact Insulation Class (IIC)

**ASTM E2235-04 (2020)**, Standard Test Method for Determination of Decay Rates for Use in Sound Insulation Test Methods

**ASTM E3222-20**, Standard Classification for Determination of High-Frequency Impact Sound Ratings

### **SECTION 4**

# MATERIAL SOURCE/INSTALLATION

The full test specimen was assembled on the day of testing by B&C. All materials provided by the client were installed on an existing B&C assembly (152 mm Concrete Slab with Suspended Ceiling) utilizing B&C-supplied materials. The assembly was installed in a steel test frame which was installed into the opening between the source and receive rooms in the test chamber. The test frame was isolated from the structure with dense neoprene gasket.

The total weight of the floor/ceiling assembly was 4256 kg. B&C will store samples of the test specimen for four years. Photographs of the test specimen are included in the report. A drawing of the test specimen is included in the report.

B&C will service this report for the entire test record retention period. Test records, such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation, will be retained by B&C for the entire test record retention period.

Unless differently required, Intertek reports apply the "Simple Acceptance" rule, also called "Shared Risk approach," of ILAC-G8:09/2019, Guidelines on Decision Rules and Statements of Conformity.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# **TEST REPORT FOR KARNDEAN DESIGNFLOORING**

Report No.: P1663.01-113-11-R0

Date: 10/05/22

# **SECTION 5**

# **EQUIPMENT**

INSTRUMENT	MANUFACTURER	MODEL	DESCRIPTION	ASSET #	CAL DA	TE
2-Channel Analog Input	National Instruments	NI 9250	2-Channel Analog Input	INT02586	04/22	*
2-Channel Analog Input	National Instruments	NI 9250	2-Channel Analog Input	INT02587	04/22	*
2-Channel Analog Input	National Instruments	NI 9250	2-Channel Analog Input	INT02608	04/22	*
2-Channel Analog Input	National Instruments	NI 9250	2-Channel Analog Input	INT02609	04/22	*
2-Channel Analog Input	National Instruments	NI 9250	2-Channel Analog Input	INT02610	04/22	*
2-Channel Analog Input	National Instruments	NI 9250	2-Channel Analog Input	INT02612	04/22	*
Microphone Calibrator	Norsonic	34093	Acoustical Calibrator	65105	10/21	
Receive Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	63741	06/22	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63740	04/22	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	64340	10/21	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63744	09/21	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	65968	01/22	
Receive Room Environmental	Comet	T7510	Temperature and Humidity	63810	10/21	
Indicator	Comet	1/510	Transmitter	63811	10/21	
Source Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	65103	02/22	
Source Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	64902	12/21	
Source Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	63739	07/22	
Source Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	63742	04/22	
Source Room Microphone	PCB Electronics	378C20	Microphone and Preamplifier	64906	04/22	
Source Room Environmental Indicator	Comet	T7510	Temperature and Humidity Transmitter	63812	10/21	
Tapping Machine	Norsonic	Nor277	Tapping Machine	INT00936	02/22	

<sup>\*</sup> The calibration frequency for this equipment is every two years per the manufacturer's recommendation.

VT RECEIVE ROOM VOLUME	155.77 m³
VT SOURCE ROOM VOLUME	190 m <sup>3</sup>

# **SECTION 6**

# **LIST OF OFFICIAL OBSERVERS**

NAME	COMPANY
Nathan Kessler	Intertek B&C
Daniel B. Mohler	Intertek B&C



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

## TEST REPORT FOR KARNDEAN DESIGNFLOORING

Report No.: P1663.01-113-11-R0

Date: 10/05/22

### **SECTION 7**

## **TEST PROCEDURE**

The microphones were calibrated before conducting the tests. The air temperature and relative humidity conditions were monitored and recorded during all measurements. The average temperature and humidity of both the source and receive rooms are listed in Sections 10 and 11. The maximum and minimum temperatures and humidities of the receive room from the duration of the test are listed in Sections 12 and 13.

The airborne transmission loss test was conducted in accordance with the ASTM E90 test method using the single direction method. Two background noise sound pressure level and five sound absorption measurements were conducted at each of five microphone positions. Two sound pressure level measurements were made simultaneously in both rooms, at each of five microphone positions.

The impact sound transmission test was conducted in accordance with the ASTM E492 test method. Two background noise sound pressure level, two sound pressure level measurements with the tapping machine operating at each position specified by ASTM E492, and five sound absorption measurements were conducted at each of five microphone positions.

Detailed test procedures, data for flanking limit tests, repeatability measurements, and reference specimen tests are available upon request.

# **SECTION 8**

### **TEST CALCULATIONS**

The STC (Sound Transmission Class), IIC (Impact Insulation Class), and HIIC (High-Frequency Impact Insulation Class) ratings were calculated in accordance with ASTM E413, ASTM E989, and ASTM E3222, respectively.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# **TEST REPORT FOR KARNDEAN DESIGNFLOORING**

Report No.: P1663.01-113-11-R0

Date: 10/05/22

# **SECTION 9**

# **TEST SPECIMEN DESCRIPTION**

MATERIAL	DIMENSIONS (mm)	THICKNESS (mm)	MANUFACTURER AND SERIES	QUANTITY	AVERAGE WEIGHT			
Flooring	1050 by 250	4.5	LooseLay LLP109	10.98 m²	7.76 kg/m²			
Flooring	Note: Loose laid							
	3023 by 3632	152.4	5000 PSI	10.98 m²	366.18 kg/m²			
Concrete Slab  Note: Installed in a test frame flush to the source room. Mats of #5 reinforcing bars were pl 25.4 mm from both the top and bottom of the slab, with bars spaced on 305 mm centers in directions. No noticeable shrinkage or cracking was visible on the specimen.								
	38.1 by 2870	43.0	Armstrong HD8906	10.9 lin m	0.45 kg/m			
Drywall Main Beam	locations and the	Note: Twelve gauge hanger wires were attached to the bottom side of the concrete at twelve locations and then to the main beams. The hanger wire was twisted around itself a minimum of three times within 76 mm creating a 305 mm plenum. The measured steel thickness was 0.5 mm.						
_	38.3 by 1219	37.3	Armstrong XL8945P	27.2 lin m	0.45 kg/m			
Cross Tee	Note: Inserted into the main beams on 610 mm centers. The measured steel thickness was 0.5 mm.							
Fiberglass	609.6 by 2438	88.9	Johns Manville Unfaced R- 13	10.98 m²	1.32 kg/m²			
Insulation Note: Loose laid onto the ceiling grid system			d system					
	3023 by 1219	15.9	National Gypsum Gold Bond® Fire-Shield® Type X	10.56 m²	11.23 kg/m²			
Gypsum Panel	Note: Fastened with 25.4 mm fine thread drywall screws on 305 mm centers. Seams and perimeter sealed with Pecora AC-20® Acoustical Sealant and covered with pressure-sensitive tape.							



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building


# **TEST REPORT FOR KARNDEAN DESIGNFLOORING**

Report No.: P1663.01-113-11-R0

Date: 10/05/22

## **SECTION 10**

# **TEST RESULTS - AIRBORNE SOUND TRANSMISSION LOSS**



	Manville Unfaced R-13 Fiberglass Insulation, 15.9 mm National Gypsum Gold Bond® Fire- Shield® Type X Gypsum Panel				
SPECIMEN AREA	10.98 m²	Receive Temp.	25°C	Source Temp.	23.3°C
TECHNICIAN	NSK	Receive Humidity	71%	<b>Source Humidity</b>	71%

FREQ	BACKGROUND	ABSORPTION	SOURCE	RECEIVE	SPECIMEN	95%	NUMBER
FREQ	SPL	ABSORPTION	SPL	SPL	TL	SAMPLING	OF
(Hz)	(dB)	m²	(dB)	(dB)	(dB)	LIMIT	DEFICIENCIES
50	36.3	25.9	107	70	35	2.9	-
63	32.3	18.0	106	65	40	5.5	-
80	32.3	13.1	103	67	36	2.8	-
100	27.2	8.8	100	66	36	1.6	-
125	31.0	9.4	103	61	44	2.0	2
160	24.1	8.8	101	59	44	1.1	5
200	21.0	11.7	97	52	47	1.7	5
250	21.3	10.7	100	49	52	1.1	3
315	20.5	9.5	104	51	55	0.8	3
400	20.2	9.0	104	49	57	1.0	4
500	18.6	8.3	100	42	60	0.7	2
630	19.6	7.8	98	39	62	0.7	1
800	17.5	8.0	99	39	62	0.7	2
1000	24.1	7.8	99	38	64	0.5	1
1250	18.9	7.8	100	36	66	0.7	0
1600	17.3	8.1	100	34	69	0.5	0
2000	14.3	8.9	100	33	70	0.5	0
2500	13.5	9.7	96	29	69	0.4	0
3150	11.8	10.2	93	23	71	0.6	0
4000	10.1	11.0	93	21	73	0.6	0
5000	9.5	12.2	92	16	76	0.6	-
6300	9.5	14.2	89	10	79	0.6	-
8000	9.7	17.1	92	10	81	0.8	-
10000	10.2	17.1	89	9	79	0.8	-
STC Ratir	1g 62	(Sound Transmi	ssion Class)		Sum o	f Deficiencies	28

Notes:

- 1) Receive Room levels less than 5 dB above the Background levels are highlighted in yellow.
- 2) Specimen TL levels listed in  $\ensuremath{\textit{red}}$  are potentially limited by the laboratory flanking limit.
- 3) Specimen TL levels listed in <u>blue</u> indicate the lower limit of the transmission loss.
- 4) Specimen TL levels listed in  $\ green \ indicate$  that there has been a filler wall correction applied



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building


# **TEST REPORT FOR KARNDEAN DESIGNFLOORING**


Report No.: P1663.01-113-11-R0

Date: 10/05/22

### **SECTION 11**

# **TEST RESULTS - AIRBORNE SOUND TRANSMISSION LOSS GRAPH**







Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building


# **TEST REPORT FOR KARNDEAN DESIGNFLOORING**

Report No.: P1663.01-113-11-R0

Date: 10/05/22

### **SECTION 12**

## **TEST RESULTS - IMPACT SOUND TRANSMISSION**



	BACKGROUND	45665571011	NODALA UTED INADA OT COL	95%	NUMBER
FREQ	SPL	ABSORPTION	NORMALIZED IMPACT SPL	SAMPLING	OF
(Hz)	(dB)	m²	(dB)	LIMIT	DEFICIENCIES
80	41.4	12.9	45	1.2	-
100	36.0	8.6	51	1.6	0
125	32.9	9.1	49	1.3	0
160	29.7	8.7	54	0.8	0
200	26.4	10.9	53	0.8	0
250	22.2	10.6	55	0.8	0
315	25.6	10.8	54	0.5	0
400	23.0	9.2	54	0.4	0
500	24.8	8.2	52	0.4	0
630	23.5	7.8	51	0.4	0
800	19.1	7.9	51	0.5	0
1000	23.7	7.9	51	0.4	1
1250	20.5	7.8	51	0.3	4
1600	18.2	8.0	50	0.3	6
2000	17.8	8.9	46	0.3	5
2500	16.7	9.7	44	0.4	6
3150	13.9	10.2	37	0.5	2
4000	11.3	11.1	30	0.8	-
5000	11.0	12.2	19	1.6	-
6300	10.5	14.4	13	1.1	-
8000	9.9	17.2	12	0.8	-
10000	10.3	17.2	12	0.7	-
IIC Ratin	<mark>g</mark> 57	(Impact Insulat	ion Class)	Sum of Deficiencie	<mark>s</mark> 24

**Notes:** Receive Room levels less than 5 dB above the Background levels are highlighted in yellow.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building


# **TEST REPORT FOR KARNDEAN DESIGNFLOORING**


Report No.: P1663.01-113-11-R0

Date: 10/05/22

### **SECTION 13**

# **TEST RESULTS - IMPACT SOUND TRANSMISSION GRAPH**







Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building


# **TEST REPORT FOR KARNDEAN DESIGNFLOORING**

Report No.: P1663.01-113-11-R0

Date: 10/05/22

# **SECTION 14**

# **TEST RESULTS - HIGH-FREQUENCY IMPACT SOUND TRANSMISSION**



	HD8906 Drywall Main Beam, 37.3 mm Armstrong XL8945P Cross Tee, 88.9 mm Johns Manville Unfaced R-13 Fiberglass Insulation, 15.9 mm National Gypsum Gold Bond® Fire-Shield® Type X Gypsum Panel				
SPECIMEN AREA	10.98 m <sup>2</sup> Maximum Temp. 25.1°C Minimum Temp. 24.9°C				
TECHNICIAN	NSK	Max. Humidity	72%	Min. Humidity	71%

FREQ	BACKGROUND SPL	ABSORPTION	NORMALIZED IMPACT SPL	95% SAMPLE CONFIDENCE	NUMBER OF
(Hz)	(dB)	m²	(dB)	LIMIT	DEFICIENCIES
400	23.0	9.2	54	0.4	0.0
500	24.8	8.2	52	0.4	0.0
630	23.5	7.8	51	0.4	0.0
800	19.1	7.9	51	0.5	0.0
1000	23.7	7.9	51	0.4	0.0
1250	20.5	7.8	51	0.3	3.0
1600	18.2	8.0	50	0.3	4.6
2000	17.8	8.9	46	0.3	4.1
2500	16.7	9.7	44	0.4	5.4
3150	13.9	10.2	37	0.5	1.2
<b>HIIC Ra</b>	ting 56	(High-Frequen	cy Impact Insulation Class)	Sum of Deficienci	es 18.4

Notes: Receive Room levels less than 5 dB above the Background levels are highlighted in yellow.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building


# **TEST REPORT FOR KARNDEAN DESIGNFLOORING**


Report No.: P1663.01-113-11-R0

Date: 10/05/22

### **SECTION 15**

# **TEST RESULTS - HIGH-FREQUENCY IMPACT SOUND TRANSMISSION GRAPH**







Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# **TEST REPORT FOR KARNDEAN DESIGNFLOORING**

Report No.: P1663.01-113-11-R0

Date: 10/05/22

# **SECTION 16**

# **PHOTOGRAPHS**



Photo No. 1 Source Room View of Test Specimen Installation



Photo No. 2
Receive Room View of Test Specimen Installation



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building


# **TEST REPORT FOR KARNDEAN DESIGNFLOORING**

Report No.: P1663.01-113-11-R0

Date: 10/05/22

# **SECTION 17**

# **DRAWING**



- 1-Floor Topping
- 2-Concrete Slab
- 3-Hanger Wire
- 4-Insulation
- 5-Ceiling Grid
- 6-Ceiling



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# **TEST REPORT FOR KARNDEAN DESIGNFLOORING**

Report No.: P1663.01-113-11-R0

Date: 10/05/22

# **SECTION 18**

# **REVISION LOG**

REVISION # DATE	PAGES	DESCRIPTION
RO 10/05/22	N/A	Original Report Issue